NORTH ELEVATION

WEST ELEVATION

EAST ELEVATION

SOUTH ELEVATION

EXTERIOR ELEVATIONS

1/8" = 1'-0"

0 4 8 16

MATERIAL KEY

MATERIAL	DESCRIPTION
EIFS	EXTERIOR INSULATED FINISH SYSTEM (SMOOTH)
TC	THIN CLAD STONE, ARRISCRAFT-GARNET SMOOTH FIN.
SS	SINGLE-SCORE 8 X 8 X 16 CMU.
MF	METAL FASCIA.
R	REVEAL (1" X 1" CLEAR ANODIZED FINISH @ 2'-0" O.C.)
CJ	CONTROL JOINT (TYPICAL, EIFS)

CANOPY KEY

MATERIAL	DESCRIPTION
CF	CANOPY FRAME - 8" STL. TUBE PAINTED
CP	CANOPY DECK- "B" DECK-NO PERFORATION

GLAZING KEY

MATERIAL	MATERIAL	COLOR / FINISH
FRAMES	ALUM.S.F.	CLEAR ANODIZED
EXTERIOR GLASS		1" BLUE REFLECTIVE GLAZING

INSULATED GLAZING SYSTEM SPECIFICATION

OLDCASTLE - 1" INSULATED GLAZING SYSTEM
U-FACTOR SUMMER DAYTIME: 0.27
SOLAR HEAT GAIN COEFFICIENT (SHGC) : 0.18

OUTBOARD: 1/4" PPG SOLARCOOL CLEAR REFLECTIVE * 2

AIRSPACE: 1/2" (AIR FILL)

INBOARD: 1/4" PPG SOLARBAN 60 ON CLEAR LOW-E * 3

1. "S" AT WINDOW LOCATIONS INDICATES SPANDREL PANELS
2. SEE WINDOW TYPES FOR LOCATIONS OF TEMPERED GLASS.

COLOR KEY

COLOR KEY OR ELEMENT	COLOR NAME	MFR / COLOR NO.
1	COUNCIL BLUFF	ICI 376
2	ONIONSKIN TAN	ICI 421
3	TURRET BROWN	ICI 321
4	WILD CRANBERRY	ICI 88
5	KHAKI	METAL SALES, (88)

CAWLEY architects
www.cawleyarchitects.com
730 N. 52nd Street
Suite 203
Phoenix, AZ 85008
602.393.5060

REGISTERED ARCHITECT CERTIFICATE NO. ... JAN CAWLEY Signed (Revised) ARIZONA, U.S.A. PRELIMINARY
EXPIRES 06/30/2017

LOT 1 at PARKWOOD RANCH MARKETPLACE

1137 SOUTH
CRISMON ROAD
MESA
ARIZONA

DATE
PRELIM. SITE PLAN 11-18-2014
PRE-APPLICATION 11-24-2014
DR - SUBMITTAL 01-05-2015
BLANKS MEETING 01-22-2015
DR RESUBMITTAL 02-03-2015

NOTICE OF ALTERNATE BILLING CYCLE:

This contract allows the owner to require submission of billings or estimates in billing cycles other than thirty days. A written description of such other billing cycle applicable to this project is available from the owner or the owner's designated agent (see owner's telephone number and address on cover sheet) and the owner or its designated agent shall provide this written description upon request.

The architectural design and data presented in these documents is an instrument of service provided by Cawley Architects.

All discrepancies found in these documents, or conflicts between these documents and actual field conditions shall be reported to Cawley Architects for resolution prior to commencement of the work.

Discrepancies between bid amounts and these documents shall be reported to the General Contractor prior to commencement of work.

Project: PKM

A7.1